Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
					Total Modified Qty	108.00			
					Total Scheduled-B Qty	170.10			
					Qty Upto 125%	108.00	Cum	85.0	9,180.00
35	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3								
	For Drain								
	From Bethel Charch to Dead End	1	230.00	1.10	1.35	341.55			
	For Road For Levelling								
	Army Compund Road	1	295.50	3.65	0.55	593.22			
					Total Modified Qty	934.77			
					Total Scheduled-B Qty	1106.19			
					Qty Upto 125%	934.77	Sqm	201.0	187888.016
36	KSRRB M200-13.1. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. II. By Mechanical Means. A. Cement Concrete Grade M-15 &M-20. MORTH Specification No. 202								
	Damaged Reaches								
	Anganawadi Surrounding Area								
	Cross Road 1	1	31.00	5.23	0.20	32.43			
	From Faisal Store	1	107.60	4.65	0.20	100.07			
	Cross Road 2	1	21.00	6.70	0.20	28.14			
	Cross Road 3	1	15.00	1.45	0.20	4.35			
	Cross Road 4	1	27.00	1.20	0.20	6.48			
	Cross Road 5	1	10.00	2.20	0.20	4.40			
	Cross Road 6	1	55.00	1.95	0.20	21.45			
	Cross Road 7	1	45.00	2.18	0.20	19.62			
	Cross Road 8	1	70.00	1.58	0.20	22.12			
	Cross Road 9	1	28.00	2.95	0.20	16.52			
	Cross Road 10	1	29.00	4.55	0.20	26.39			
	Cross Road 11	1	70.00	1.78	0.20	24.92			
	Chowtry Surrounding								
	Cross Road 1	1	35.00	3.60	0.20	25.20			
	Cross Road 2	1	45.00	4.00	0.20	36.00			
	Cross Road 2	1	10.00	4.55	0.20	9.10			
	Cross Road 3	1	12.00	3.45	0.20	8.28			
	Cross Road 4	1	12.00	5.05	0.20	12.12			
	Cross Road 5	1	28.00	4.55	0.20	25.48			
	Cross Road 6	1	23.00	2.05	0.20	9.43			
	From Charch	1	124.00	3.55	0.20	88.04			
	Army Compund Road	1	205.50	2.81	0.20	115.49			
	In front of Chowtry	1	47.00	6.00	0.20	56.40			
	Anganawadi	1	12.00	6.50	0.20	15.60			
	Cross Road 1	1	66.00	3.05	0.20	40.26			
	Cross Road 2	1	40.00	3.83	0.20	30.64			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross Road 3	1	60.00	5.25	0.20	63.00			
	In Front of Devi Temple	1	13.00	11.25	0.20	29.25			
	Devi Temple Surrounding								
	Cross Road 1	1	50.00	2.38	0.20	23.80			
	Cross Road 2	1	18.00	0.95	0.20	3.42			
	Cross Road 3	1	88.00	1.60	0.20	28.16			
	Cross Road 4	1	16.00	1.80	0.20	5.76			
	Cross Road 5	1	24.00	1.20	0.20	5.76			
	Cross Road 6	1	24.00	2.95	0.20	14.16			
	Cross Road 7	1	13.00	1.70	0.20	4.42			
	Cross Road 8	1	40.00	1.88	0.20	15.04			
	Cross Road 9	1	30.00	3.75	0.20	22.50			
	Cross Road 10	1	40.00	2.13	0.20	17.04			
	Cross Road 11	1	50.00	1.58	0.20	15.80			
	Cross Road 12	1	20.00	1.60	0.20	6.40			
	Cross Road 13	1	47.00	1.88	0.20	17.67			
	Arallimara Surrounding Area								
	Cross Road 1	1	96.00	5.40	0.20	103.68			
	Ambedkar Statue Road	1	324.00	3.40	0.20	220.32			
	Anthony Charch Surrounding Area								
	Cross Road 1	1	104.00	3.00	0.20	62.40			
	Cross Road 2	1	111.00	2.55	0.20	56.61			
	Cross Road 3	1	60.00	1.25	0.20	15.00			
	Cross Road 4	1	27.00	1.40	0.20	7.56			
	Cross Road 5	1	70.00	1.60	0.20	22.40			
	Cross Road 6	1	45.00	1.38	0.20	12.42			
	Cross Road 7	1	40.00	2.35	0.20	18.80			
	Chamundeshwary Temple	1	25.00	4.45	0.20	22.25			
	In Front of Prayer Hall	1	13.00	7.25	0.20	18.85			
	Cross Road 1	1	85.00	1.95	0.20	33.15			
	Cross Road 2	1	37.00	1.45	0.20	10.73			
	Cross Road 3	1	40.00	1.85	0.20	14.80			
	Cross Road 4	1	30.00	2.50	0.20	15.00			
	Cross Road 5	1	10.00	3.00	0.20	6.00			
	Cross Road 6	1	26.00	1.65	0.20	8.58			
	Cross Road 7	1	35.00	1.50	0.20	10.50			
	Cross Road 8	1	38.00	1.15	0.20	8.74			
	Cross Road 9	1	11.00	0.90	0.20	1.98			
	Cross Road 10	1	15.00	1.20	0.20	3.60			
	Cross Road 11	1	15.00	1.20	0.20	3.60			
	Cross Road 12	1	13.00	1.20	0.20	3.12			
	Cross Road 13	1	130.00	1.19	0.20	30.94			
	Cross Road 14	1	50.00	1.20	0.20	12.00			
	In Front of Bala Yeshu Mandir	1	21.00	1.70	0.20	7.14			
					Total Modified Qty	1781.28			
					Total Scheduled-B Qty	1454.47			
					Qty Upto 125%	1781.28	Sqm	504.00	897763.61

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
37	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregtes @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications.								
	Bottom								
	From Bethel Charch to Dead End	1	230.00	1.10	0.15	37.95			
					Total Modified Qty	**37.95**			
					Total Scheduled-B Qty	**112.25**			
					Qty Upto 125%	**37.95**	**Cum**	**5900.00**	**223905.000**
38	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - Ready mixed Cement concrete for Beams, Staircase and Roof with M-20								
	Drain Bottom								
	From Bethel Charch to Dead End	1	230.00	1.10	0.10	25.30			
	Side Walls								
	From Bethel Charch to Dead End	2	230.00	0.15	0.90	62.10			
					Total Modified Qty	**87.40**			
					Total Scheduled-B Qty	**258.77**			
					Qty Upto 125%	**87.40**	**Sqm**	**6805.0**	**594757.00**
39	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications.								
	Side Walls								
	From Bethel Charch to Dead End	4	230.00		0.90	828.00			
					Total Modified Qty	**828.00**			
					Total Scheduled-B Qty	**2546.50**			
					Qty Upto 125%	**828.00**	**Sqm**	**330.00**	**273240.000**
40	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 (P.No.17, I.No.4.46.2)								
					Total Modified Qty	**5.64**			
					Total Scheduled-B Qty	**17.15**			
					Qty Upto 125%	**5.64**	**Sqm**	**65000.00**	**366600.00**
41	providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc.., comlete.10cm thick								
					Total Modified Qty	**0.00**			
					Total Scheduled-B Qty	**633.60**			
					Qty Upto 125%	**0.000**	**Cum**	**855.00**	**0.00**
42	Providing machine cutting of BS Slab including all lead and lift as per direction of engineer -in charge of work -data rate								

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
					Total Modified Qty	0.00			
					Total Scheduled-B Qty	3906.00			
					Qty Upto 125%	0.00	Nos	65.00	0.00
43	providing precast slab of 250mm thick including cost of all materials , labour,curing,transportation, loading, unloading, etc., complete as per the dorection of engineer in charge								
					Total Modified Qty	0.00			
					Total Scheduled-B Qty	37.80			
					Qty Upto 125%	0.00	No	5495.00	0.00
44	Excavation for road work in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location to a lead of 1.00k.m and complete as per specifications								
					Total Modified Qty	0.00			
					Total Scheduled-B Qty	727.24			
					Qty Upto 125%	0.00	No	163.00	0.00
45	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregtes @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery,								
	Anganawadi Surrounding Area								
	Cross Road 1	1	31.00	5.23	0.10	16.21			
	From Faisal Store	1	107.60	4.65	0.10	50.03			
	Cross Road 2	1	21.00	6.70	0.10	14.07			
	Cross Road 3	1	15.00	1.45	0.10	2.18			
	Cross Road 4	1	27.00	1.20	0.10	3.24			
	Cross Road 5	1	10.00	2.20	0.10	2.20			
	Cross Road 6	1	55.00	1.95	0.10	10.73			
	Cross Road 7	1	45.00	2.18	0.10	9.81			
	Cross Road 8	1	70.00	1.58	0.10	11.06			
	Cross Road 9	1	28.00	2.95	0.10	8.26			
	Cross Road 10	1	29.00	4.55	0.10	13.20			
	Cross Road 11	1	70.00	1.78	0.10	12.46			
	Chowtry Surrounding								
	Cross Road 1	1	35.00	3.60	0.10	12.60			
	Cross Road 2	1	45.00	4.00	0.10	18.00			
	Cross Road 2	1	10.00	4.55	0.10	4.55			
	Cross Road 3	1	12.00	3.45	0.10	4.14			
	Cross Road 4	1	12.00	5.05	0.10	6.06			
	Cross Road 5	1	28.00	4.55	0.10	12.74			
	Cross Road 6	1	23.00	2.05	0.10	4.72			
	From Charch	1	124.00	3.55	0.10	44.02			
	Army Compund Road	1	205.50	2.81	0.10	57.75			
	In front of Chowtry	1	47.00	6.00	0.10	28.20			
	Anganawadi	1	12.00	6.50	0.10	7.80			
	Cross Road 1	1	66.00	3.05	0.10	20.13			
	Cross Road 2	1	40.00	3.83	0.10	15.32			
	Cross Road 3	1	60.00	5.25	0.10	31.50			
	In Front of Devi Temple	1	13.00	11.25	0.10	14.63			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Devi Temple Surrounding								
	Cross Road 1	1	50.00	2.38	0.10	11.90			
	Cross Road 2	1	18.00	0.95	0.10	1.71			
	Cross Road 3	1	88.00	1.60	0.10	14.08			
	Cross Road 4	1	16.00	1.80	0.10	2.88			
	Cross Road 5	1	24.00	1.20	0.10	2.88			
	Cross Road 6	1	24.00	2.95	0.10	7.08			
	Cross Road 7	1	13.00	1.70	0.10	2.21			
	Cross Road 8	1	40.00	1.88	0.10	7.52			
	Cross Road 9	1	30.00	3.75	0.10	11.25			
	Cross Road 10	1	40.00	2.13	0.10	8.52			
	Cross Road 11	1	50.00	1.58	0.10	7.90			
	Cross Road 12	1	20.00	1.60	0.10	3.20			
	Cross Road 13	1	47.00	1.88	0.10	8.84			
	Arallimara Surrounding Area					0.00			
	Cross Road 1	1	96.00	5.40	0.10	51.84			
	Ambedkar Statue Road	1	324.00	3.40	0.10	110.16			
	Anthony Charch Surrounding Area								
	Cross Road 1	1	104.00	3.00	0.10	31.20			
	Cross Road 2	1	111.00	2.55	0.10	28.31			
	Cross Road 3	1	60.00	1.25	0.10	7.50			
	Cross Road 4	1	27.00	1.40	0.10	3.78			
	Cross Road 5	1	70.00	1.60	0.10	11.20			
	Cross Road 6	1	45.00	1.38	0.10	6.21			
	Cross Road 7	1	40.00	2.35	0.10	9.40			
	Chamundeshwary Temple	1	25.00	4.45	0.10	11.13			
	In Front of Prayer Hall	1	13.00	7.25	0.10	9.43			
	Cross Road 1	1	85.00	1.95	0.10	16.58			
	Cross Road 2	1	37.00	1.45	0.10	5.37			
	Cross Road 3	1	40.00	1.85	0.10	7.40			
	Cross Road 4	1	30.00	2.50	0.10	7.50			
	Cross Road 5	1	10.00	3.00	0.10	3.00			
	Cross Road 6	1	26.00	1.65	0.10	4.29			
	Cross Road 7	1	35.00	1.50	0.10	5.25			
	Cross Road 8	1	38.00	1.15	0.10	4.37			
	Cross Road 9	1	11.00	0.90	0.10	0.99			
	Cross Road 10	1	15.00	1.20	0.15	2.70			
	Cross Road 11	1	15.00	1.20	0.15	2.70			
	Cross Road 12	1	13.00	1.20	0.11	1.72			
	Cross Road 13	1	130.00	1.19	0.10	15.47			
	Cross Road 14	1	50.00	1.20	0.15	9.00			
	In Front of Bala Yeshu Mandir	1	21.00	1.70	0.15	5.36			
					Total Modified Qty	**897.38**			
					Total Scheduled-B Qty	**727.24**			
					Qty Upto 125%	**897.38**	Sqm	5630.00	5052246.59

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
46	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. - M20 (at 300Kg per cum coarse aggregate @ 0.64cum and fine aggregate @ 0.43cum)								
	Anganawadi Surrounding Area								
	Cross Road 1	1	31.00	5.23	0.17	27.56			
	From Faisal Store	1	107.60	4.65	0.18	87.56			
	Cross Road 2	1	21.00	6.70	0.18	24.62			
	Cross Road 3	1	15.00	1.45	0.15	3.26			
	Cross Road 4	1	27.00	1.20	0.15	4.86			
	Cross Road 5	1	10.00	2.20	0.15	3.30			
	Cross Road 6	1	55.00	1.95	0.15	16.09			
	Cross Road 7	1	45.00	2.18	0.15	14.72			
	Cross Road 8	1	70.00	1.58	0.15	16.59			
	Cross Road 9	1	28.00	2.95	0.18	14.46			
	Cross Road 10	1	29.00	4.55	0.15	19.79			
	Cross Road 11	1	70.00	1.78	0.15	18.69			
	Chowtry Surrounding								
	Cross Road 1	1	35.00	3.60	0.15	18.90			
	Cross Road 2	1	45.00	4.00	0.15	27.00			
	Cross Road 2	1	10.00	4.55	0.15	6.83			
	Cross Road 3	1	12.00	3.45	0.15	6.21			
	Cross Road 4	1	12.00	5.05	0.15	9.09			
	Cross Road 5	1	28.00	4.55	0.15	19.11			
	Cross Road 6	1	23.00	2.05	0.15	7.07			
	From Charch	1	124.00	3.55	0.15	66.03			
	Army Compund Road	1	205.50	2.81	0.15	86.62			
	In front of Chowtry	1	47.00	6.00	0.15	42.30			
	Anganawadi	1	12.00	6.50	0.18	13.65			
	Cross Road 1	1	66.00	3.05	0.15	30.20			
	Cross Road 2	1	40.00	3.83	0.15	22.98			
	Cross Road 3	1	60.00	5.25	0.15	47.25			
	In Front of Devi Temple	1	13.00	11.25	0.18	25.59			
	Devi Temple Surrounding								
	Cross Road 1	1	50.00	2.38	0.15	17.85			
	Cross Road 2	1	18.00	0.95	0.15	2.57			
	Cross Road 3	1	88.00	1.60	0.15	21.12			
	Cross Road 4	1	16.00	1.80	0.15	4.32			
	Cross Road 5	1	24.00	1.20	0.15	4.32			
	Cross Road 6	1	24.00	2.95	0.15	10.62			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross Road 7	1	13.00	1.70	0.15	3.32			
	Cross Road 8	1	40.00	1.88	0.15	11.28			
	Cross Road 9	1	30.00	3.75	0.15	16.88			
	Cross Road 10	1	40.00	2.13	0.15	12.78			
	Cross Road 11	1	50.00	1.58	0.15	11.85			
	Cross Road 12	1	20.00	1.60	0.15	4.80			
	Cross Road 13	1	47.00	1.88	0.15	13.25			
	Arallimara Surrounding Area								
	Cross Road 1	1	96.00	5.40	0.15	77.76			
	Ambedkar Statue Road	1	324.00	3.40	0.18	192.78			
	Anthony Charch Surrounding Area								
	Cross Road 1	1	104.00	3.00	0.15	46.80			
	Cross Road 2	1	111.00	2.55	0.15	42.46			
	Cross Road 3	1	60.00	1.25	0.15	11.25			
	Cross Road 4	1	27.00	1.40	0.15	5.67			
	Cross Road 5	1	70.00	1.60	0.15	16.80			
	Cross Road 6	1	45.00	1.38	0.15	9.32			
	Cross Road 7	1	40.00	2.35	0.15	14.10			
	Chamundeshwary Temple	1	25.00	4.45	0.15	16.69			
	In Front of Prayer Hall	1	13.00	7.25	0.15	14.14			
	Cross Road 1	1	85.00	1.95	0.15	24.86			
	Cross Road 2	1	37.00	1.45	0.10	5.37			
	Cross Road 3	1	40.00	1.85	0.10	7.40			
	Cross Road 4	1	30.00	2.50	0.10	7.50			
	Cross Road 5	1	10.00	3.00	0.10	3.00			
	Cross Road 6	1	26.00	1.65	0.10	4.29			
	Cross Road 7	1	35.00	1.50	0.15	7.88			
	Cross Road 8	1	38.00	1.15	0.15	6.56			
	Cross Road 9	1	11.00	0.90	0.10	0.99			
	Cross Road 10	1	15.00	1.20	0.10	1.80			
	Cross Road 11	1	15.00	1.20	0.10	1.80			
	Cross Road 12	1	13.00	1.20	0.10	1.56			
	Cross Road 13	1	130.00	1.19	0.10	15.47			
	Cross Road 14	1	50.00	1.20	0.10	6.00			
	In Front of Bala Yeshu Mandir	1	21.00	1.70	0.10	3.57			
						Total Modified Qty	**1361.07**		
						Total Scheduled-B Qty	**1090.85**		
						Qty Upto 125%	**1361.07**	cum	**6744.00**	**9179023.03**
47	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.								
	Anganawadi Surrounding Area								
	Cross Road 1	1	31.00	5.23		162.13			
	From Faisal Store	1	107.60	4.65		500.34			
	Cross Road 2	1	21.00	6.70		140.70			
	Cross Road 3	1	15.00	1.45		21.75			
	Cross Road 4	1	27.00	1.20		32.40			
	Cross Road 5	1	10.00	2.20		22.00			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross Road 6	1	55.00	1.95		107.25			
	Cross Road 7	1	45.00	2.18		98.10			
	Cross Road 8	1	70.00	1.58		110.60			
	Cross Road 9	1	28.00	2.95		82.60			
	Cross Road 10	1	29.00	4.55		131.95			
	Cross Road 11	1	70.00	1.78		124.60			
	Chowtry Surrounding								
	Cross Road 1	1	35.00	3.60		126.00			
	Cross Road 2	1	45.00	4.00		180.00			
	Cross Road 2	1	10.00	4.55		45.50			
	Cross Road 3	1	12.00	3.45		41.40			
	Cross Road 4	1	12.00	5.05		60.60			
	Cross Road 5	1	28.00	4.55		127.40			
	Cross Road 6	1	23.00	2.05		47.15			
	From Charch	1	124.00	3.55		440.20			
	Army Compund Road	1	205.50	2.81		577.46			
	In front of Chowtry	1	47.00	6.00		282.00			
	Anganawadi	1	12.00	6.50		78.00			
	Cross Road 1	1	66.00	3.05		201.30			
	Cross Road 2	1	40.00	3.83		153.20			
	Cross Road 3	1	60.00	5.25		315.00			
	In Front of Devi Temple	1	13.00	11.25		146.25			
	Devi Temple Surrounding								
	Cross Road 1	1	50.00	2.38		119.00			
	Cross Road 2	1	18.00	0.95		17.10			
	Cross Road 3	1	88.00	1.60		140.80			
	Cross Road 4	1	16.00	1.80		28.80			
	Cross Road 5	1	24.00	1.20		28.80			
	Cross Road 6	1	24.00	2.95		70.80			
	Cross Road 7	1	13.00	1.70		22.10			
	Cross Road 8	1	40.00	1.88		75.20			
	Cross Road 9	1	30.00	3.75		112.50			
	Cross Road 10	1	40.00	2.13		85.20			
	Cross Road 11	1	50.00	1.58		79.00			
	Cross Road 12	1	20.00	1.60		32.00			
	Cross Road 13	1	47.00	1.88		88.36			
	Arallimara Surrounding Area								
	Cross Road 1	1	96.00	5.40		518.40			
	Ambedkar Statue Road	1	324.00	3.40		1101.60			
	Anthony Charch Surrounding Area								
	Cross Road 1	1	104.00	3.00		312.00			
	Cross Road 2	1	111.00	2.55		283.05			
	Cross Road 3	1	60.00	1.25		75.00			
	Cross Road 4	1	27.00	1.40		37.80			
	Cross Road 5	1	70.00	1.60		112.00			
	Cross Road 6	1	45.00	1.38		62.10			
	Cross Road 7	1	40.00	2.35		94.00			
	Chamundeshwary Temple Sourrounding Area	1	25.00	4.45		111.25			
	In Front of Prayer Hall	1	13.00	7.25		94.25			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross Road 1	1	85.00	1.95		165.75			
	Cross Road 2	1	37.00	1.45		53.65			
	Cross Road 3	1	40.00	1.85		74.00			
	Cross Road 4	1	30.00	2.50		75.00			
	Cross Road 5	1	10.00	3.00		30.00			
	Cross Road 6	1	26.00	1.65		42.90			
	Cross Road 7	1	35.00	1.50		52.50			
	Cross Road 8	1	38.00	1.15		43.70			
	Cross Road 9	1	11.00	0.90		9.90			
	Cross Road 10	1	15.00	1.20		18.00			
	Cross Road 11	1	15.00	1.20		18.00			
	Cross Road 12	1	13.00	1.20		15.60			
	Cross Road 13	1	130.00	1.19		154.70			
	Cross Road 14	1	50.00	1.20		60.00			
	In Front of Bala Yeshu Mandir	1	21.00	1.70		35.70			
		1	41.00	1.65		67.65			
					Total Modified Qty	**8974.04**			
					Total Scheduled-B Qty	**7272.35**			
					Qty Upto 125%	**8974.04**	**Sqm**	**46.00**	**412805.61**
48	Providing groove cutting for width of 5mm to 10mm and depth 80mm- 100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. - for concrete pavement								
	Anganawadi Surrounding Area								
	Cross Road 1	1	31.00			31.00			
	From Faisal Store	1	107.60			107.60			
	Cross Road 2	1	21.00			21.00			
	Cross Road 3	1	15.00			15.00			
	Cross Road 4	1	27.00			27.00			
	Cross Road 5	1	10.00			10.00			
	Cross Road 6	1	45.00			45.00			
	Cross Road 7	1	45.00			45.00			
	Cross Road 8	1	70.00			70.00			
	Cross Road 9	1	28.00			28.00			
	Cross Road 10	1	29.00			29.00			
	Cross Road 11	1	70.00			70.00			
	Chowtry Surrounding								
	Cross Road 1	1	35.00			35.00			
	Cross Road 2	1	45.00			45.00			
	Cross Road 2	1	10.00			10.00			
	Cross Road 3	1	12.00			12.00			
	Cross Road 4	1	12.00			12.00			
	Cross Road 5	1	28.00			28.00			
	Cross Road 6	1	23.00			23.00			
	From Charch	1	124.00			124.00			
	Army Compund Road	1	205.50			205.50			
	In front of Chowtry	1	47.00			47.00			
	Anganawadi	1	12.00			12.00			
	Cross Road 1	1	66.00			66.00			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross Road 2	1	40.00			40.00			
	Cross Road 3	1	60.00			60.00			
	In Front of Devi Temple	1	13.00			13.00			
	Devi Temple Surrounding								
	Cross Road 1	1	50.00			50.00			
	Cross Road 2	1	18.00			18.00			
	Cross Road 3	1	88.00			88.00			
	Cross Road 4	1	16.00			16.00			
	Cross Road 5	1	24.00			24.00			
	Cross Road 6	1	24.00			24.00			
	Cross Road 7	1	13.00			13.00			
	Cross Road 8	1	40.00			40.00			
	Cross Road 9	1	30.00			30.00			
	Cross Road 10	1	40.00			40.00			
	Cross Road 11	1	50.00			50.00			
	Cross Road 12	1	20.00			20.00			
	Cross Road 13	1	47.00			47.00			
	Arallimara Surrounding Area								
	Cross Road 1	1	96.00			96.00			
	Ambedkar Statue Road	1	324.00			324.00			
	Anthony Charch Surrounding Area								
	Cross Road 1	1	104.00			104.00			
	Cross Road 2	1	111.00			111.00			
	Cross Road 3	1	60.00			60.00			
	Cross Road 4	1	27.00			27.00			
	Cross Road 5	1	70.00			70.00			
	Cross Road 6	1	45.00			45.00			
	Cross Road 7	1	40.00			40.00			
	Chamundeshwary Temple Sourrounding Area	1	25.00			25.00			
	In Front of Prayer Hall	1	13.00			13.00			
	Cross Road 1	1	85.00			85.00			
	Cross Road 2	1	37.00			37.00			
	Cross Road 3	1	40.00			40.00			
	Cross Road 4	1	30.00			30.00			
	Cross Road 5	1	10.00			10.00			
	Cross Road 6	1	26.00			26.00			
	Cross Road 7	1	35.00			35.00			
	Cross Road 8	1	38.00			38.00			
	Cross Road 9	1	11.00			11.00			
	Cross Road 10	1	15.00			15.00			
	Cross Road 11	1	15.00			15.00			
	Cross Road 12	1	13.00			13.00			
	Cross Road 13	1	130.00			130.00			
	In Front of Bala Yeshu Mandir	1	21.00						
	Cross Road 14	1	50.00			50.00			
	Horizontal Groove Cuting								
	Chowtry Surrounding								
	Cross Road 1	1	35.00			35.00			
	Cross Road 2	1	45.00			45.00			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross Road 2	1	10.00			10.00			
	Cross Road 3	1	12.00			12.00			
	Cross Road 4	1	12.00			12.00			
	Cross Road 5	1	28.00			28.00			
	Cross Road 6	1	23.00			23.00			
	From Charch	1	124.00			124.00			
	In front of Chowtry	1	47.00			47.00			
	Cross Road 1	1	66.00			66.00			
	Cross Road 2	1	40.00			40.00			
	Cross Road 3	1	60.00			60.00			
	In Front of Devi Temple	1	13.00			13.00			
	Arallimara Surrounding Area								
	Cross Road 1	1	96.00			96.00			
	Ambedkar Statue Road	1	324.00			324.00			
					Total Modified Qty	4076.10			
					Total Scheduled-B Qty	3264.30			
					Qty Upto 125%	4076.10	Cum	136.00	554349.60
49	providing and erecting direction and place indentification retro-reflectorised sign as per IRC:67-2012 Made of high intensity grade sheeting vide clause 800.1.3 fixed over aluminiuam sheeting, 2mm thick with area exceeding 0.9sqm supported on mild steel angle iron post 75mmx75mmx6mm, 2Nos. Firmly fixed to ground by means of properly designed foundtation with M-15 Grade cement concrete 45cm x45cm x 60cm 60cm below ground level as per approved drawing complete as per specifications. MORTH Specification No.801 Using type IV Sheeting								
						0.00			
					Total Modified Qty	0.00			
					Total Scheduled-B Qty	2.00			
					Qty Upto 125%	0.00	Cum	8072.00	0.00
								Total Excecuted Cost	29176420.82
									10,003.18
								GRAND TOTAL	29186424.00

Assistant Engineer,
Ward No-16
BBMP,Bangalore

Asst. Executive Engineer,
Yeswanthpura Sub Division
BBMP,Bangalore

Executive Engineer,
R.R.Nagara Division
BBMP,Bangalore

Scanned by CamScanner